



# Cold Linac NPM status

*Forum diags ESS at Lund  
November 20<sup>th</sup> 2018*

*CEA Saclay: P. Abbon, F. Belloni, F. Benedetti, G. Coulloux,  
C. Lahonde-Hamdoun, P. Le Boulout, P. Legou,  
Y. Mariette, J. Marroncle, J.P. Mols, V. Nadot,  
L. Scola*

*ESS Lund: C. Thomas (NPM Project Leader)*

*IPHI team for her collaborative spirit*



# Outline




What since last diagnostics forum?

- First beam test at IPHI
- Working meeting at ESS
- Second beam test at IPHI

Analysis in progress for CDR

Toward CDR

Planning





# First Beam test at IPHI

Feb. 13<sup>th</sup> to April 12<sup>th</sup> 2018

IPHI: (Injecteur de Protons à Haute Intensité or  
Proton Injector at High Intensity)

Proton beam accelerator at CEA Saclay

- 3 MeV -  $I_p < 100$  mA – up to cw
- RF = 352 MHz
- Injector: 95 keV



# Life is a long, but a quiet river...



## Delays

Component deliveries with important delays

- Most of them were postponed by few weeks, even months wrt the delivery date  
the worst: last MCP received on January 4<sup>th</sup> 2018 (ordered on 29/6/17)

Vacuum: Problem with a leakage vacuum detector

Etc.

➔ No time to test MCPs in laboratory, just an overlook on CCD cameras, HVs, Faster (strips)...

## Installation on IPHI (Feb. 13<sup>th</sup> 2018)

**Kind of IPHI commissioning:** working for the first time with an inner diagnostics. Starting data taking completely blind, but a FC, 2 ACCTs upstream and downstream the RFQ and BPMs not connected

- Problem with HVs (sparking)
- impossibility to work with Photonis pMCP, we gave up in mid March, send it back to Photonis and recovered it July 11<sup>th</sup> 2018 → finally no beam test with a 2<sup>nd</sup> pMCP!



# DAQ, FEE & CS



Caramel and Syroco: delivered at Saclay by LPC Caen (end 8/17)  
Adaptation card for signal read-out

## Cameras

- NPM (2): Epics development
- FPM (1): brought by Cyrille Thomas
- Scintillating screen: Iphi

ISEG HVs:  $\pm 6$ ,  $-15/+15$  and  $-30/+30$  kV delivered

- potentiometer for MCP gain
- Connection boxes for vHV


Motor for moving scintillating screen: GeoBrick is installed and checked.



# On deviated line




Profile measurement on Y direction for avoiding dispersive plane!






Actuator with 3  
scintillating screens

the 3 IPMs







Electric field cage:  
Frame, support...



Macor<sup>®</sup>  
frame



MCP



strips

anode




# 1<sup>st</sup> beam!



Finally, beam appears on March 1<sup>st</sup> 2018!


Beam direction



but... it appears clearly that beam was moving top/bottom by few mm, and comes back regularly (several seconds)...

...like electric charging / discharging materials!

1 or 2 weeks later, BPMs were connected →









# pMCP (Hamamatsu) + CCD



## Double Gaussian fit





# MCP and constant strips




## MCP (Hamamatsu) + constant strips







Read-Out: D. Etasse et al., Faster system  
LPC Caen, France.

## Comparison MCP+strips/CCD

$I_{\text{beam}} = 32\text{mA} - 10^{-7}\text{mbar} - \Delta t = 100\mu\text{s} (1\text{Hz}) - \sigma \approx 3.3\text{mm}$



### Profile positions: CCD/Strips/BPM





# Toward a second IPHI test



First IPHI test results were presented at Lund during a Working Meeting on July 18<sup>th</sup>

Requested more time to study particularly:

- Space charge effect:  $\sigma_x$  for applying SC algorithm (Francesca & Cyrille)
- Interferences between two IPMs with perpendicular electric field ( $\vec{E}_X, \vec{E}_Y$ )
- Electric field homogeneity
- Reducing sparking
- Extrapolation IPHI data to ESS  $\rightarrow$  feasibility
- Read-Out choice: more data have to be taken with strip RO
- Etc.

Therefore, the test bench was a bit different

- IPM1 in X direction ( $\neq$ width strips), IPM2 (Y-Photonis pMCP) and IPM3 (constant width strips)
- Grids in front of RO (thin mesh)




# Second Beam test at IPHI

Sept. 10<sup>th</sup> ... Oct. 19<sup>th</sup> 2018, with few days

IPHI: (Injecteur de Protons à Haute Intensité or  
Proton Injector at High Intensity)

Proton beam accelerator at CEA Saclay

- 3 MeV -  $I_p < 100$  mA – up to cw
- RF = 352 MHz
- Injector: 95 keV





# Preamble





During Sept. 10<sup>th</sup> to Oct. 19<sup>th</sup>, we share the beam with other teams. Devoted time to NPM was about 2 weeks

Beamline was assembled to test a BPM of ESS Bilbao upstream to the NPM test bench. In order to protect the BPM (electrodes), a water cooling collimator with a 25 mm aperture was mounted upstream the BPM. Lot of electron background was generated.

collimator (inner  $\phi$  25mm)



Beam prints on interceptive scintillating screen.






# First beam



First beam was delivered on September 14 → the profile was directly measured  
Reminder: it took 2 weeks for the 1<sup>st</sup> beam test!



proton beam




# Few preliminary results



- Analysis is under progress -

This nice picture gives an idea about the quality of the electric field uniformity






# Few preliminary results (2)




05/10/2018:  $I_{\text{beam}} = 20\text{mA}$  and  $\Delta t_{\text{pulse}} = 500\mu\text{s}$

X profile with a « Gaussian » strips



Y profile with pMCP from Photonis



Improvement of HV connection to increase electric field

Analysis under progress:



- electron background subtraction → hopeless to work in “electron mode”
- Extrapolation to ESS condition → this time the residual gas pressure was quite low ( $5 \cdot 10^{-8}$  mbar)
- Electric field uniformity
- SC
- Etc.

Goal: CDR on Feb. 5<sup>th</sup> 2019




# Toward CDR

- Background from the beam → calculation by Mamad: important to determine the background which is supposed to pollute profiles
- Change request: grounded disks for IPM → Daresbury (letter sent by Cyrille on Feb. 2017)...  
CEA Saclay proposition sent to Paul on April 2018
- Improvement to be done on the final IPM → feedback from our tests and also from CDR




Hypothesis: seems that we are going to choose pMCP + CCD

- CCD: not radiation hard
  - CID camera (less sensitive...)
  - Camera set at remote distance → fiberscope (multi o.f. bundle for imaging) → see Cyrille Thomas who plan to test soon the radiation hardness of cheaper ones
  - Deposited power 1 to 10 Gy/h (Report ESS 00602018 – 1/2017)
- pMCP
  - Follow-up software with reference channels → correction on-line
  - MCP lifetime duration
    - We learnt that Photonis has developed new MCPs increasing their lifetime
    - We have proposed a specific assembling in order to replace them quickly and efficiently.






# pMCP replacement: IPM<sub>y</sub>





# pMCP replacement: IPM<sub>x</sub>




## IPM assembling, test and validation

- Assembling in a clean room and test/validation
  - Design of a new vacuum chamber, to test:
    - Vacuum pressure  $10^{-9}$  mbar
    - HV sustaining 20, 30 kV
    - RGA (Residual Gas Analyzer) to be compliant with outgassing requirements
    - Check FEE electronics with a  $\beta$  source
- Plan to have a meeting with Saclay people working on CM (ok)

## IPM storage / sending to Lund


- Storage pot  $N_2$ , vacuum



2018

2019

2020



we are here!

document delivery → 4/12/2020



# Summary



## NPM data taking

1<sup>st</sup> IPHI test → Working Meeting on July 2018 at Lund

2<sup>nd</sup> IPHI test → analysis is in progress for CDR around Feb. 5<sup>th</sup> 2019

→ Lot of work done, starting from scratch

## CDR preparation

Starting to work on MCP and CCD Read-Out compliant to ESS radiation environment

Change request: grounded disks

Improvement of IPM

Assembling, test and Validation in clean room

Wrapping of IPM for Lund delivery

... a long way!



# EMU repairing

O. Tuske, N. Misiara, P. Daniel-Thomas



# Damage 1: Transportation



Damage 1: happens during the EMU transportation between CEA Saclay (Dec. 8<sup>th</sup> 2016) and INFN Catania (Dec. 12<sup>th</sup> 2016)

The bellow of the EMU has been damaged in its wooden box

The wounded undulations of the bellow have been bended back in Catania premises.

Leak test before and after: no leak!

→ **INFN takes the risk to used it**

*ESS will pay for a new bellow  
CEA STAFF will make the change as soon as EMU is back to Saclay.*

[CEA-ESS-DIA-NC-0001.pdf]





# Damage 2: translation problem




Damage 2: once INFN Catania has installed the EMU on the LEBT end, they encountered translation problem on July 21<sup>st</sup> 2017

The measurement head has crashed into the diagnostic chamber

- Ceramic connectors bent
- Collector connectors twisted...

*INFN STAFF made the reparation* 😊

They fixed it as well as they could to resume test measurement activities.





# Damage 3: Thermal problem



Damage 3: during measurements on the proton source beam at Catania, a thermal damage most likely (since no data available) caused by a too much focalized beam onto the EMU beam dump and slit (27/11/2017) induced a scratch on the beam dump and the closure of the slit aperture.

AS no-DATA was send to CEA to explain how this incident occurs, we can only guess that the power density of the beam was much higher than expected / requested.

*THE SLITS have been damaged: leaks on pipe/slit brazing...*

*ESS pays for a new slit*

*CEA staff installed it freely*

*The beam STOPPER was marked but still functional*

[CEA-ESS-DIA-NC-0023.pdf]





# Repairing at CEA Saclay



EMU back to Saclay on November 23<sup>rd</sup> 2017



Replacing the bellow, the outer shield, the connectors with ceramics.  
Removing water pipes with great care for the O-ring joints, connections...

CEA Saclay exchanges the damage slits by its own subsystem

Several tests were done fulfilling the requirements as vacuum and water leaks

→ **Finally, EMU n°2 was sent to Lund on mid-October 2018.**

ESS should refund the slit subsystem





Thank you for your attention