

# Implementation of icBLM algorithms

dr inż. Grzegorz Jabłoński, dr inż. Wojciech Jalmużna, dr inż. Rafał Kiełbik



13.02.2019



# icBLM BEE hardware platform IOxOS IFC\_1410

FPGA Processing Unit

Xilinx Kintex UltraScale KU040 FPGA+1024MB dual channel DDR3L

**Processor Unit** 

High-performance Freescale/NXP QorIQ T2081 processor On-board 2GB DDR3L 1866 SDRAM Powered by U-Boot/Linux and able to run EPICS-based applications

**FMC** Interfaces

Dual HPC VITA-57.1-compliant FMC slots

#### AMC Interface

Port 0: AMC.2-compliant gigabit Ethernet link with the processor Ports 4 to 7: AMC.1-compliant PCI express x4 Gen3 link with the FPGA Ports 12 to 15: point-to-point LVDS links with the FPGA Ports 17 to 20: shared bus M-LVDS links with the FPGA





# icBLM BEE hardware platform PICO 4

- High Resolution multichannel current measurements up to ±10 mA (different versions available)
- 4 Current-Input Channels -Bipolar
- 1 MSPS simultaneous and independent sampling
- 20-bit Resolution
- Floating up to 300 V







### **Implementation status**







# Hardware-software interface

- Using circular buffers in DRAM to stream data to CPU
- Using TSCR interface for control and algorithm parameters
- Both DDR bank (currently) via SMEMDIR interface @275MHz, 1900 MB/s bandwidth
- Not needing such large Block RAMs overlapping initial part of DDR







# Data transmission protocol layers

- Circular buffers stream of unstructured data
- Data frames timestamping and integrity check
- Periodic data content-specific header





### Frame layout

- Start-of-frame pattern
- Timestamp
  - Serial number of the 1-microsecond window
  - Sample index within the window.
- 1 generic information byte
- 16-bit number of samples in the frame
- Payload packed back-to-back on the bit level without any additional padding
- 32-bit CRC of all the previous words in the frame followed by the End-of-frame pattern.







# **Circular Buffer Implementation**



- Read pointer, write pointer for each channel
- Overflow not able to write data to DDR at given input data rate
- Overwrite data readout by DMA too slow



- Read pointer at the moment of overwrite recorded



# Solved problems

#### • DDR Calibration

The TOSCA framwork has had a bug, causing segmentation violation errors on the host CPU during the on-board DDR memory calibration procedure most of the time. Several reboots of the IFC\_1410 modules were needed to make the board operate properly. The problems became more severe after migration of the Vivado version from 2016.4 to 2018.2. The problem has been finally identified by IOxOS and fixed in December 2018

#### • Timing closure problems

The examples provided by IOxOS do not synthesize without timing errors "out of a box". Most implementation runs of our project resulted in pulse width timing violations related to the 250 MHz clock driving the DDR memory controller. Finally we have been able to fix the problem by constraining the global buffer output driving this clock to a specific location. With this constraint, the memory clock can be increased to 275 MHz.





## Solved problems

#### • DMA performance problems

Initially we were instructed to use the Tosca kernel driver for the communication between CPU and FPGA. This driver provided very low DMA throughput of order of 550 MiB/s. Later on we have transitioned to the ESS-Tsc driver with the throughput of 950 MiB/s.





 Loss of data during simultaneous DMA transfers from both DDR banks

There is a bug in the TOSCA firmware or device driver causing data loss when the DMA transfer is performed simultaneously from two different memory banks using different DMA channels from different threads. The workaround is protections of the DMA transfer function in the userspace program by mutex, but this solution reduces performance.





• Tsc driver not supporting scatter-gather operations and prone to resource leaks

Tsc driver has high performance, but requires allocation of contiguous physical memory buffers for operation. When memory is fragmented, it is not possible to allocate these memory buffers and a CPU reboot is required. Tosca driver did not have this problem, but it offered much lower performance. These memory buffers have to be manually allocated and are not freed automatically when the device file is closed. It requires appropriate signal handlers in the userspace program to avoid resource leaks.





• Problems with PCIe Gen3 link to Concurrent CPU

The PCIe link speed between Concurrent CPU and the IOxOS board alternates between Gen1 and Gen3 after each system reboot.





- No separate interrupt support for both memory banks Only one interrupt, common for both memory banks, is supported. It is a firmware issue and will be fixed.
- Tsc Driver cannot access PON space when run on Concurrent CPU

TscMon (and custom software applications) fail to access registers placed on PON configuration space (such as Power On for FMC cards) when run on Concurrent CPU. The same software and TscMon commands can be successfully run on embedded IFC1410 processor. The bug prevents proper behaviour of the software when only one PCIe endpoint (to Concurrent) is present in the design. Reportedly can be fixed by the PON FPGA firmware update.





### **Current status**

Raw data acquisition for 4 ADC channels





### 10 kHz Raw Data







### 10 kHz Raw Data - Spectrum



http://www.dmcs.p.lodz.pl



### 100 kHz Raw Data







### 100 kHz Raw Data - Spectrum







# Thank you for your attention

