

DE LA RECHERCHE À L'INDUSTRIE



Experience from IPHI

*RFQ mini-workshop Cavity & Beam Dynamics &
Strategies for Higher Current Commissioning*

N. Chauvin*, on behalf of the IPHI team.

*Nicolas.Chauvin@cea.fr

CEA, Université Paris-Saclay, F-91191
Gif-sur-Yvette, France.

February 25, 2022

www.cea.fr



- 1 The IPHI Facility, a High Intensity Proton Injector
- 2 LEBT Commissioning
- 3 RFQ Beam Commissioning
- 4 MEBT Commissioning and Experiments with IPHI
- 5 Conclusions and Perspectives

1 The IPHI Facility, a High Intensity Proton Injector

- IPHI Overview
- SILHI Ion Source
- LEBT
- RFQ
- MEBT

2 LEBT Commissioning

3 RFQ Beam Commissioning

4 MEBT Commissioning and Experiments with IPHI


5 Conclusions and Perspectives

IPHI Main Parameters

A demonstrator of a 100 mA CW proton injector


Main parameters

- ECR ion source and LEBT: 100 mA, 95 keV, pulsed or cw
- 4-vanes RFQ: 100 mA, 3 MeV, 352 MHz
- Power sources: 2 klystrons of more than 1 MW
- 2 beam lines: straight line with beam dump and a deflected line with dipole magnet.




SILHI Ion Source Main Parameters

- Developed in Saclay since 1994
- 2.45 GHz ECR ion sources
- Particles: H^+ , D^+ , He^+
- Pulsed to c.w. beam
- Designed for 100 mA H^+ pulsed or c.w.
- SILHI-like source developped for IFMIF and FAIR proton linac





2.45 GHz SILHI ion source



Low Energy Beam Transport (LEBT) Line

The IPHI LEBT:



- Dual solenoid focusing scheme
- Sterrers to correct beam misalignment
- Beam diagnostics (DCCT, ACCT, CCD Camera, Insulated Beam Stopper)
- Iris to control/limit beam size and intensity



IPHI 4-Vanes RFQ

<i>Parameter</i>	<i>Value</i>
Particle	H^+
Max. Current [mA]	100
Frequency [MHz]	352
Input Energy [keV/u]	95
Output Energy [MeV/u]	3
RFQ length [m]	6
Duty Cycle [%]	cw


- R&D program for high intensity beams (CEA/CNRS/CERN)
- Segmented in 6 sections
- Mech. tolerances $\pm 30 \mu m$
- Commissioned in 2016 in pulsed mode



Medium Energy Beam Transport (MEBT) Line

Medium energy beam lines

- RFQ output section 1: 3 quadrupoles
- Dipole magnet 28.5°
- Straight section: 2 quadrupoles and 300 kW beam dump
- Deflected line: 2 quadrupoles and beam stopper or experiment



1 The IPHI Facility, a High Intensity Proton Injector

2 **LEBT Commissioning**

- LEBT Layout
- Simulation Strategy
- Simulation vs Experience


3 RFQ Beam Commissioning

4 MEBT Commissioning and Experiments with IPHI

5 Conclusions and Perspectives

SILHI source & LEBT

Experimental Setup



SILHI source & LEBT setup

- LEBT with 2 solenoids
- Total length: 3.5 m
- RFQ injection cone
- Emittancemeter (Allison scanner) and Faraday Cup at the end of the beam line

Simulation strategy

- ❶ **Experiment: optimization** of the beam transmission through the cone. Solenoids values are fixed.
- ❷ **Experiment: emittance** measurement.
- ❸ **Simulation:** using TraceWin, **adjustment** of the beam initial conditions (α, β, ϵ) and degree of SCC to **fit** to the measured emittance.
- ❹ **Simulation:** using TraceWin with the fitted parameters determination of **optimal solenoid values** for RFQ injection.
- ❺ **Experimental validation:** Emittance measurement.

This method is simple and independent of:


- Self-consistent SCC simulations (time consuming)
- Ion source beam distribution simulation

- **PRO:** An empirical model that is easy to use
- **CONS:** Lack of physics in the model


Simulation vs Experience

Emittance Measurement

$$I_{CF} = 30 \text{ mA}$$




Experiment $\varepsilon = 0.17 \pi \cdot \text{mm} \cdot \text{mrad}$



Simulation $\varepsilon = 0.15 \pi \cdot \text{mm} \cdot \text{mrad}$

Simulation vs Experience

Emittance vs Beam Intensity




SILHI LEBT simulations


- Simulations give a quite good agreement with data
- Model has to be tested with a 100 mA beam
- Validation with SCC self consistent code (Warp) is needed

Simulation Results

LEBT Transmission vs Solenoid Magnetic Field



Experiment



Simulation


Beam intensity: 40 mA

- Reasonable agreement.
- Discrepancies: alignment and steerers.
- RFQ optimal injection $\neq$ Maximal LEBT transmission


- 1 The IPHI Facility, a High Intensity Proton Injector
- 2 LEBT Commissioning
- 3 RFQ Beam Commissioning**
 - RFQ Commissioning
 - Beam Commissioning at Low Power
 - Beam Commissioning at High Beam Power
- 4 MEBT Commissioning and Experiments with IPHI
- 5 Conclusions and Perspectives

RF Conditioning

- Conditioning started in April 2015 limited by the cooling system of the RFQ (duty cycle limited to 1%)
- After technical issues, conditioning restarted in February 2016 until 1.2 MW peak with a duty cycle of 0.5%
- April 2016: first beam accelerated: Intensity = 60 mA at 0.4% d. c.
- Mid-2018: nominal voltage reached at 5% d. c.
- End 2018: RF platform upgrade (pulsed klystron, installation/test a new CW klystron), RFQ cooling system upgrade
- Mid-2019: RF tuners have been replaced
- September 2019: nominal voltage reached at 50% d. c.



April 2016: First Beam Accelerated




Results obtained

- Transmission through the RFQ in 2016: 93% – Now: 96%.
- Accelerated beam in 2016: Intensity = 60 mA at 0.4% duty cycle.
- Output beam energy (3 MeV) was checked with dipole magnetic field.
- October 2018: beam power of 7 kW was accelerated.

Transmission vs RFQ Voltage


Low Beam Power



- Measurement performed for a ≈ 70 mA proton beam at the RFQ injection
- Two measurements: before (2017) and after (2019) tuner replacement

RFQ Transmission vs LEBT Solenoids Tuning

Experimental Setup



Experimental conditions







- 80 mA H^+ beam from the source (total extracted current ≈ 100 mA) then reduced by iris
- Duty cycle: 10^{-4} (100 μ s at 1 Hz) $\rightarrow$ beam pulses achieved by RFQ (2 ms pulses from the source) – RFQ as a chopper...
- Data taken for several iris aperture

Simulation model

- Initial LEBT model established during LEBT commissioning + RFQ simulation
- The input Twiss parameters have been optimized (within 15%) and SCC (within 5%) to minimize the experimental/simulation spread
- It has been found that the solenoids magnetic field have to be increased by 8% to minimize the experimental/simulation spread
 $\rightarrow$ Solenoids field measurement is needed to confirm that.

RFQ Transmission vs LEBT Solenoids Tuning

Experiment vs Simulation for Iris aperture 90 mm




Beam Commissioning

Beam Power Ramp-up

September - October 2019


- The extracted beam power was gradually ramped-up to 80 kW.
- Peak current at RFQ output: 50–55 mA.
- The duty cycle was increased from a few % to 50 %.
- The beam was sent to the beam dump (direct beam line).



Pulses: 7 ms @ 50 Hz

$$I_{H^+} = 50 \text{ mA}$$

**Beam Power =
52.5 kW**




- 1 The IPHI Facility, a High Intensity Proton Injector
- 2 LEBT Commissioning
- 3 RFQ Beam Commissioning
- 4 MEBT Commissioning and Experiments with IPHI**
 - IPHI MEBT Setup
 - Experiments with IPHI 2019 – 2020
 - Toward a 30 kW Experiment 2021 – 2022
 - The 30 kW Experiment – 2022
- 5 Conclusions and Perspectives

IPHI MEBT Setup


Two Beam Lines

- A straight line to a beam dump (300 kW)
- An experimental line (deflection 28.5°)



Target Tests for Neutron Production

- 21 mA pulsed beam: pulses of 2.85 ms @ 17 Hz
- 5 targets testes, 239 hours of beam on targets
- A target tested up to 115 mA.h, 5.5 kW
- Beam size: ≈ 11 mm RMS – $\langle P \rangle_{max} \approx 0.5$ kW cm $^{-2}$



Integrated Power on Targets

Toward a 30 kW Experiment 2021 – 2022

Goals

- Tests of a higher power neutron production target
- Required power on target: 30 kW
- Beam Intensity ≈ 30 mA
- Duty cycle: 10 ms pulses @33 Hz
- Beam on target during 100 hours
- Beam size on target: $\sigma_x = 15$ mm / $\sigma_y = 20$ mm



IPHI MEBT Commissioning @30 kW

- Commissioning with a 30 kW beam transported in the experimental line (28.5°)
- Stability tests for "long runs"

Toward a 30 kW Experiment 2021 – 2022


First Beam Tests

- Array of thermocouples along the beam line
- Power ramp-up to 30 kW to the beam dump (straight line)
- Several days later: a hole in the beam line @20 kW before Q3




Incident Analysis

- Small increase of beam current before hole (instability)
- BPMs signal remained stable
- Data archiving: 2 s resolution
- No signal on neutron beam loss monitors



Thermal Calculations

- Beam "spot" around $\varnothing 6$ mm on the beam pipe
- For 85 W power lost: 1 hour
- For 200 W power lost: 1 mn
- At 10 cm of the hot spot $\approx 45^\circ\text{C}$ after 1 hour for 85 W power lost
- Difficult to record a sudden increase of beam beam loss (200 W) at more than 1 cm



Power Ramp-up Strategy


Beam Trajectory Correction

Secure the Beam Position at Low Duty Cycle

- Measurements at nominal intensity (35 mA) and 10^{-4} duty cycle
- Magnetic steerers field measurement (field maps were wrong !)
- Test of the BPMs with a new electronic + IPHI electronic calibration
- Cross check of the beam position measurements with a SEM grid
- Beam alignment in quad center to minimize dipolar kicks


Duty Cycle increase

- Keep the BPM signal constant with the duty cycle increase
- Thermal camera monitoring
- Keep the measured temperatures below 28°C



Beam Transport

Measurements vs Simulation @ SEM Grid Position 1



Beam Profile Measurements

- SEM grid from GANIL (44 tungsten wires with 1 mm step)
- Measurement on RF axis, before dipole
- Measurements at nominal beam intensity (35 mA) and 10^{-4} duty cycle (≈ 10 W)


Beam Dynamics Simulation

- Input beam distribution coming from RFQ simulation
- Quadrupole field maps in agreement with field measurement

Beam Transport

Measurements vs Simulation @ SEM Grid Position 1

Beam Intensity: 34 mA – Quad triplet = 0 A



Measured Profile

$$\sigma_x = 7.8 \text{ mm}$$

$$\sigma_y = 9.6 \text{ mm}$$

Gaussian Fit

$$\sigma_x = 8 \text{ mm}$$

$$\sigma_y = 12.3 \text{ mm}$$

Simulation


$$\sigma_x = 7.4 \text{ mm}$$

$$\sigma_y = 9.0 \text{ mm}$$

Beam Transport

Measurements vs Simulation @ SEM Grid Position 1

Beam Intensity: 34 mA – Q1=-47 A / Q2=75 A / Q3=-45 A



Measured Profile

$$\sigma_x = 5.3 \text{ mm}$$

$$\sigma_y = 7.9 \text{ mm}$$

Gaussian Fit

$$\sigma_x = 5.2 \text{ mm}$$

$$\sigma_y = 8.9 \text{ mm}$$


Simulation

$$\sigma_x = 4.7 \text{ mm}$$

$$\sigma_y = 7.2 \text{ mm}$$

Beam Transport

Measurements vs Simulation @ SEM Grid Position 2 and 3




Beam Profile Measurements

- Measurement with SEM 2 in the beam line (permanent position)
- Measurement with SEM 3 at target position

Beam Transport

Measurements vs Simulation @ SEM Grid Position 2

Beam Intensity: 34 mA – Q4=-3.7 A / Q5=11.2 A



Measured Profile

$$\sigma_x = 7.2 \text{ mm}$$

$$\sigma_y = 10.8 \text{ mm}$$

Gaussian Fit

$$\sigma_x = 7.7 \text{ mm}$$

$$\sigma_y = 16.3 \text{ mm}$$

Simulation


$$\sigma_x = 7.7 \text{ mm}$$

$$\sigma_y = 12.0 \text{ mm}$$

Beam Transport

Measurements vs Simulation @ SEM Grid Position 3 (Target)

Beam Intensity: 34 mA – Q4=-3.7 A / Q5=11.2 A



Measured Profile

$$\sigma_x = 10.8 \text{ mm}$$

$$\sigma_y = 11.7 \text{ mm}$$

Gaussian Fit

$$\sigma_x = 16.6 \text{ mm}$$


$$\sigma_y = 30.5 \text{ mm}$$

Simulation

$$\sigma_x = 12.3 \text{ mm}$$

$$\sigma_y = 13.0 \text{ mm}$$

Beam Intensity: 34 mA – Q4=-3.7 A / Q5=11.2 A



**Simulated Beam Size on
Target**

$$\sigma_x = 15.8 \text{ mm}$$


$$\sigma_y = 20 \text{ mm}$$

SEM grid measurement range (-19 mm – + 23 mm) is too small for the beam size...


**Simulated Beam Distribution on
Target**

Beam Transport

Simulation of Beam Transport in the MEBT Line



Beam density in X plane



Beam density in Y plane

Thermal Tests on Al Target

- 2 days of experiment at 30 kW (with a maximum @ 37 kW beam power)
- Final beam centring on target (temperature measurement)
- Thermomechanical calculations validation

Final Experiment with Be Target

- 10 days of experiment ($\approx$ 10 hours beam time per day)
- Average beam power around 27 kW (limitation due to the target)
- A few technical problems (power supply, control system) but no problem with the beam
- More than 100 hours of beam time integrated on target
- On the last day/night: 24 hours of beam without major stops (a few sparks at the ion source)

- 1 The IPHI Facility, a High Intensity Proton Injector
- 2 LEBT Commissioning
- 3 RFQ Beam Commissioning
- 4 MEBT Commissioning and Experiments with IPHI
- 5 Conclusions and Perspectives**

Conclusions and Perspectives

Conclusions

- IPHI beam commissioning has been done up to 80 kW beam power during a short time
- IPHI beam commissioning has been done up for a reliable operation with a 30 kW beam power
- The beam transport in the whole accelerator has been simulated
- A neutron production experiment has been performed with more of 100 hours of beam time on target

Lesson Learned and Perspectives

- We were too optimistic, at the beginning, with a high power beam
- Lack of interlock and MPS on IPHI (will be added)
- RFQ bead-pull measurement and tuning
- A 3 MeV emittancemeter (slit-grid) is under development
- Replacement of diagnostics (never enough diags...) is planned
- A chopper for the LEBT is under development

The Whole Team !



... an those who are not on the picture: C. Alba-Simionesco, B. Bolzon, R. Braud, J. Darpentigny, C. Doira, C. Deberles, R. Duperrier, G. Exil, Y. Gauthier , F. Gibert, E. Giner-Demange, A. Gomes, T. Hamelin, K. Jiguet, E. Jorgji, W. Josse, O. Kuster, R. Lautie, P. Lavie, A. Letourneau, A. Marchix, C. Marchand, A. Menelle, K. Paunac, P. Permingeat, E. Petit, O. Piquet, F. Porcher, B. Pottin, F. Prunes, O. Sineau, L. Thulliez, H. N. Tran, D. Uriot.



Thank you for your attention !