

# Heimdal Instrument @ ESS Diffraction STAP May 2022

## Dan Mannix

Lead Scientist Heimdal Instrument ESS, Lund Sweden




ESS May 2022



# HEIMDAL – Hybrid Diffraction

Multi Length Scale Neutron Scattering Instrument:

$10^{-2} - 10^8$  nm



# The Heimdal Risk Register



<p>RISKS to Heimdal project: Delay, Quality &amp; Costs</p>	<p>Lack of Engineering resources based at ESS. Lead Engineer is only Engineering resource, based in Denmark. Close to retirement age. No Engineering manpower based at ESS.</p>	<p>Heimdal cannot complete engineering documentation according to schedule. Lead engineer retiring and not enough overlap with replacement engineer. Risk of delay and quality of final instrument.</p>	<p>Delay in instrument schedule. Quality of Instrument delivered. Increased labor costs from delay.</p>
<p>RISKS to Heimdal project: Delay, Quality &amp; Costs</p>	<p style="text-align: center; background-color: red; color: white; font-weight: bold; font-size: 24px;">20</p>	<p style="text-align: center; font-weight: bold; font-size: 18px;">Reduce</p>	<p>Allocation of Engineering resources to Heimdal and based at ESS. Best solution is reuse of engineering resources from earlier instruments with ESS instrument work experience.</p>

Heimdal Requires more engineering support based at ESS to deal with large workload & installation

Kåre Iversen - Lead Engineer based at Aarhus University  
 Dan Mannix - Lead Scientist based at ESS

# The Heimdal Risk Register



Risk of personnel leaving	Neutron instrument division has requested opening of Heimdal lead scientist position	Dec-20	Low	Unlikely	2	4	Falling
Delay of 2D Detector Procurement from PSI	Issue resolved and moving ahead in 2022. Guide procurement priority (Change in BOT ESS-MS). Detector procurement Q2 Q3 2022.	2020-12-01	Low	Moderate	4	6	Falling
Delay of Guide procurement from PSI	Issue resolved and moving ahead in 2022. PSI Guide tender publication expected Q2 2022. RISK Reduced	2020-12-01	Low	Moderate	4	6	Falling
SANS upgradability	Partners and ESS shall clarify the subject as soon as possible. If the proposed changes are not excepted there has to be some plan that allows a later upgrade with reasonable budget.	2022 Q2	High	Likely	16	15	Rising
T0 Cost / High Background	Search new supplier of T0 chopper. ESS to investigate if it can be built by ESS. Update Feb-22: ESS Chopper group scope. Risk		Very low	Moderate	2	15	Falling
delay to cave installation	Awaiting results of rebaseline	2020-12-15	Low	Moderate	4		New


# Change Request to include more cold guide scope



Item	Contractor	Costed	Within Budget ?
Chopper Systems	ESS Common	Yes	Yes
T0 Chopper	ESS	Yes	Yes
Guide Shielding	ESS Common	Yes	Yes
Cave Shielding	Mirrotron	Yes	Yes
Detector	CDT	No	Yes ? Reduce coverage if needed
Monitors	ESS Common	Yes	Yes
Guide Optics	Tender published May 2022	No	Depends of how much cold guide ?

By end of 2022 we should know all real costs and know how much cold guide can be bought


# Heimdal Timeline



5

Instruments in User Program

BOT & HC 3 9 15  
FS SOUP




New Build Focus for Instrument:

Delay to BOT & Longer open access to bunker

Procurement of Bunker components:

- Thermal Choppers
- TO Chopper
- Guide Optics, Support & Vacuum Housings
- Heavy Shutter
- Light Shutter

# Heimdal Timeline



5


## Instruments in User Program

BOT & HC FS SOUP 3 9 15

Open Bunker ~20m




# Heimdal inside Bunker Components



Bunker Wall Feedthrough  
(Guide procurement PSI)

Thermal Neutron Choppers  
(ESS Chopper Group)

Light Shutter  
(AU)  
(Next priority)




Cold Neutron  
Choppers  
(upgrade)


T0 Chopper  
(ESS Chopper Group)

Heavy Shutter (AU)  
(Next priority)

# NBOA Project: Swiss Neutronics




Reduced window thickness  
from 2mm to 1.5



Optics sTG3 finalised – Ready for Manufacture



NBPI in queue with other ESS instruments

Installation expected before BOT Q4 2023.






# Heimdal Choppers

ESS Common Chopper Project  
Expected Before BOT Q3 2023  
Project within Budget



# T0 Chopper





Prototype T0 Chopper Design

Construction with ESS Chopper Group - within budget

Final modified design for Heimdal approved by ESS

Scope transfer from IFE to ESS

Installation ? Maybe after BOT (shutdown 2026). Start with no T0 and vacuum tube.



Guide adjusting  
flange milled to 110  
mm square

CF63 /  $\phi 113.5$  mm


120 mm between  
support frame and  
T0 bottom






# T0 simulation results



- A T0 chopper is placed leaving 11 mm of the guide space below the hammer open.
- Streaming of neutrons below the hammer is absent beyond 35 meters from target (figure for  $E_n > 20\text{MeV}$ )
- Same background as for full-sized T0
- Radiation safety fulfilled: guide shielding is designed to provide 1.5 uSv/h outside with T0 parked open.
- 300 uSv/h contact dose rate at T0 hammer 1h after shutdown, well within 10mSv/h limit.



# Light Shutter (BBG)




Procurement AU: Next Priority  
Delivery before BOT Q4 2023



# Heavy Shutter

Procurement AU: Next Priority  
Delivery before BOT Q4 2023



Open position




Closed position




# Heavy Shutter









Ground level






Platform level






Roof level






Ground level




Platform level




Roof level





# Cave Shielding Calculations



## Neutronics Calculations – Optimising costs

90cm concrete walls (Diffraction).


40cm concrete walls (SANS)

70cm concrete roof (Diffraction)

30cm Concrete roof (SANS)


Beam stop Steel Bar inside heavy concrete

H1H2 Scenarios approved (Feb. 2020)



# Heimdal Guide Procurement (PSI)




PAUL SCHERRER INSTITUT		Project <b>ESS-HEIMDAL</b>				
System name <b>HEIMDAL Neutron Guides and Housings</b>		Document identification <b>PSI-ESS-SU33-001</b>				
Type document Requirements specification	Author Dan Mannix      Co-Author(s)    Uwe Stuhr					
		Revision index (Address)	<b>1.0</b>			
<p><b>Summary</b></p> <p>This document specifies the requirements for the detailed technical design, manufacturing and installation of a sub-systems of the neutron beam delivery system for the HEIMDAL instrument at the ESS, that are being specified and acquired by PSI as Swiss In-Kind partner. The relevant components represent the neutron optics of the instrument, more specifically the neutron guides, their vacuum housings, interfaces and supports.</p>  <p>The HEIMDAL team, through PSI, has provided general guide geometries, coating requirements and envelope. The contractor will be responsible for the detailed design and production of the optics components as well as the vacuum vessel containing them. On the ESS site, the optics will be installed and aligned by the contractor consistently with the access plans provided by the ESS.</p> <p>The product specification is divided sections termed as 'included', 'optional' and 'excluded'. This is because certain cold guide sections have been designated as too expensive or technically challenging to be included in a later upgrade stage of the Heimdal instrument and form part of this tender along with the total thermal guide 'included' sections. In particular, complete sections inside the bunker are considered as high priority 'options' due to their completion complexity after neutron production at ESS. Therefore, the bidder must provide a cost breakdown of the 'included' thermal and 'option' cold guide sections together with the vacuum housings and supports and <i>should</i> provide a cost breakdown for the total cold guide system including 'excluded' sections. Ultimately, this procurement is aimed at purchasing as much of heimdal thermal and cold guide systems allowed by WTO rules. The contractor must also provide a coherent final detailed design, for both the total thermal and cold guides systems along with a consistent installation plan of the guide systems and project management plan.</p>						
Organization	Amount	email address	Approved by (name):	Responsible for:	Date	Signature
PSI	1	ronald.dettwiler@psi.ch	Artur Glavic Uwe Stuhr	PSI-ESS Project Sub-Project Leader		
<b>Release</b>				Released revisions:		
Name		Function	Date	Signature		
Ronald Dettwiler		QA				
Gabor Laszlo		ESS CTV responsible				
Alex Amato		Division Head NUM				
Template	PSI-MESH-006		Date:	Name of author	Signature of author	
Rev:	Rev. 1.00			Dan Mannix		

Current priority for Heimdal  
Tender Publication May 2022.

Thanks to PSI, Procurement Department  
Uwe Stuhr & Artur Glavic


# D03 Heimdal Merge of Guides



# Heimdal Guide (PSI)

- (1) Complete detailed design of Thermal & Cold guide systems
- (2) Complete costing of thermal guides optics & housings
- (3) Options 1 Cold guide sections in-bunker & long straight
- (4) Options 2 Cold Guide Sections pre-cave

Final project aligned with budget ?



Scope Change request:  
Installation of cold guide  
**In-bunker + long straight**




Upgrade - Pre-cave.



# Heimdal Detector System



## $^{10}\text{B}$ Based Jalousie Detector



Technical Specification May 2022

ESS Dream -> Magic -> Heimdal

Procurement to start May 2022 After Guides with PSI


PSI -> Hopefully not full open tender (only one supplier)

# Heimdal General Sample Environment

## Cooling



Orange Cryo  
1.5K-300K



Dilution  
~10s mK

## Heating



cryofurnace  
1.5K-600K (800K)

## Magnetic Field



Cryo-magnetic  
8-Tesla

## Pressure ? What ?




~~Paris Edinburh  
Diamond Anvil + Heat  
Stress/Strain Cell~~

Discussion – Malcolm  
SAD Group

## Electro-chemistry



## Diffraction



SANS

# Heimdal Fast Sample Environments High Throughput Neutron Scattering



## Open Flow Cooling




### Oxford Cryosystems:

N<sub>2</sub> cryo system  
80-500 K

### Cryo Industries America:

Cryocool-LHe : 10-600 K  
Consumption: 2L/hour 10 K  
Cold zone: 10 mm  
Cool down time: 10 min

## Induction Heating



- Electromagnetic radiation
- Fast heating
- High temperature >1370 °C

## Hot Air Blower




### 1000 W system

### 40 L/m dry air

- RT - 1000 K in 100s
- combined with
- flow system
- active cooling by dry air
- => fast sample change

+ Robot sample changer



Nordforsk proposal 2020

Heimdal/Dream compatible sample environment

- Fast Heating

+ ~~Post Doc Started @ AU:~~


**Jakob Voldum Ahlburg**

# HEIMDAL Polarised Neutrons

## ESS Polarised Neutron Workshop

Design for Polarised Neutrons on Heimdal  
 Cold guide supermirror  
 Thermal Guide  $^3\text{He}$  Cell


Keep open possibility for future




Neutron

Total Spin:  $-\frac{1}{2} + \frac{1}{2} + \frac{1}{2} = \frac{1}{2}$

Total Charge:  $+\frac{2}{3} - \frac{1}{3} - \frac{1}{3} = 0$



Polarised Thermal Neutrons  
 incident + analysis



Polarised Cold Neutrons  
 Incident + Analysis

# Heimdal Continues to Make Progress



Thank  
you