



**The Commissioning Workshop of  
ESS- J-PARC collaboration**

**10-12 October, 2022**

# **J-PARC's Accelerator construction, commissioning and operation (400MeV-linac, 3GeV-ring) -I**

**Hidetomo Oguri**

**J-PARC Center  
Japan Atomic Energy Agency (JAEA)**

## **\*The 1st day:**

- J-PARC's accelerator construction, commissioning and operation
  - 400MeV Linac, 3GeV-ring (H. Oguri, Y. Liu)

## **\*The 2nd day:**

- Experience with machine protection system at J-PARC (N. Hayashi)
- Experience with control tools at J-PARC (H. Takahashi)
- Beam commissioning at the MLF target station (S. Meigo)
- Recent progress in LLRF (K. Futatsukawa)
- Experiences of klystron operation (Y. Fuwa)
- Status of accelerating cavities (Y. Kondo)
- Status of beam monitor for linac (K. Moriya)



## ● Linac

- **H<sup>-</sup> beam** acceleration
- Beam energy : **400 MeV**
- Beam current:  
**50 mA** for user operation  
**60 mA** for beam study  
(peak current at linac exit)
- Pulse length : < 0.5 ms
- Repetition: 25 Hz

## ● Rapid Cycling Synchrotron (RCS)

- Charge-exchange injection **H<sup>-</sup> → H<sup>+</sup>**
- Beam energy : **3 GeV**
- Injection into MR
- Delivery to MLF
- Beam supply to MLF with the beam power of **740 kW** (in 2021)

## ● Main Ring (MR)

- Beam energy : **30 GeV**
- Beam power:  
**510 kW** (in 2021) to NU  
**64 kW** (in 2021) to HD

# Construction and operation history




Year	Event
2002	<ul style="list-style-type: none"><li>• Linac bldg. construction start</li><li>• MR bldg. construction start</li><li>• RCS bldg. construction start</li></ul>
2005	<ul style="list-style-type: none"><li>• RCS bldg. is completed</li><li>• Linac bldg. is completed</li></ul>
2006	<ul style="list-style-type: none"><li>• Beam commissioning start (Linac)</li></ul>
2007	<ul style="list-style-type: none"><li>• 181 MeV acceleration is achieved at linac</li><li>• MR bldg. is completed</li><li>• 3 GeV acceleration is achieved at RCS</li></ul>
2008	<ul style="list-style-type: none"><li>• 30 GeV acceleration is achieved at MR</li></ul>
2014	<ul style="list-style-type: none"><li>• Linac upgrade (energy &amp; intensity) plan is completed</li></ul>
2015	<ul style="list-style-type: none"><li>• Single shot mode operation with a beam power equivalent to 1MW is achieved</li></ul>
2018	<ul style="list-style-type: none"><li>• Continuous operation with a beam power equivalent to 1 MW is succeeded</li></ul>

# Construction (linac)

Jun-4, 2004



Aug-23, 2005



Jun-1, 2005



**\* Nov-20, 2006:  
Commissioning start**  
**\* Jan- 24, 2007:  
181 MeV is achieved**

# Construction (RCS)



Jul-14, 2004



Aug-23, 2005



Jul-17, 2005



**\*Sep., 2007:  
Commissioning start**  
**\*Oct- 31, 2007:  
3 GeV is achieved**

# Construction (MR)

Oct-1, 2004



Dec-15, 2005



Dec-13, 2005




**\*May, 2008:**  
**Commissioning start**  
**\*Dec- 23, 2008:**  
**30 GeV is achieved**

# Linac upgrade (energy)

- To suppress the space-charge effect, which limits the obtainable beam power at the RCS, the beam energy from the linac was increased from **181 MeV** to **400 MeV** by adding **ACS cavities** in 2014.

## □ History of the ACS

- In the end of 2010, the first mass-produced ACS module was completed and its high-power test was performed.
  - Only five of the 25 total modules could be tested before the installation due to the huge earthquake in 2011.
- In Aug. 2013, installation to the beam line was started.
  - It took one day to complete for one ACS cavity.
- In Nov. 2013, high-power conditioning was started.
  - An average conditioning time is 149 hours.
- In Dec. 2013, the beam commissioning was started.
  - **400 MeV was achieved in Jan. 2014.**



## Beam intensity at RCS

By increasing the injection energy, the beam loss was dramatically reduced.  
 ( $\sim 30\% \rightarrow <1\%$ )






# Linac upgrade (intensity)

- A front-end part (ion source & RFQ) was replaced for increasing peak beam current from 30 mA to 50 mA in 2014.

## Ion source

- To achieve 50 mA, we changed the type of ion source from the arc-discharge to the RF-discharge for source plasma production.

	Previous IS	Present IS
Source plasma production	Arc discharge (LaB <sub>6</sub> filament), (Cs free)	RF discharge (int. antenna), (Cs injection)
H <sup>+</sup> beam current	20mA (user op) 32mA (max)	60mA (user op) 72mA (max)
Cont. op. time	~1,000 hours @20mA	4,001 hours @60mA



## RFQ

- At the beginning of the J-PARC linac operation, an RFQ with a design current of 30 mA was used. To achieve 1 MW, we replaced the new RFQ with a design current of 50 mA.
- The major engineering change between the two is the design of the RF cavity structure.



- The RF cavity is installed in a large vacuum vessel. It is difficult to obtain good vacuum quality because the surface area is very large.




- Vacuum-tight cavity structure is adopted. To this end, we adopted brazing for the assembly method.

# **Operation status (Linac, RCS)**


# Accelerator status for one year (JFY2021)



Facility	User time [h]	Net time [h]	Beam power [kW]	Availability [%]
MLF	3,608	3,480	630/740	96.4
Neutrino (FX)	371	347	~ 510	93.6
Hadron (SX)	1,016	952	Max. ~64	93.7




# Linac beam intensity



## Operation history of the linac beam intensity

- In 2008, MLF user operation started with linac beam current of **5mA**.
- In 2009, beam current was increased to **15mA** and operated for about next five year.
- In 2014, after linac upgrade was completed, **30mA** operation started.
- In 2018, **50mA (nominal)** operation was started.

# RCS beam power




- In JFY2022, 800-kW beam is delivered to the MLF with **>95 %** availability.

# Continuous operation with 1MW (linac)



At the end of June 2020, we conducted continuous operation with 1MW for about 40 h.


## Time variation of output voltage of each HVDC power supply



## Down time:

- HVDC power supply: 0 min
- Accelerating cavity: ~ 6 min  
(This data is not shown on this slide)

## Comparison of residual dose at 1-MW and 600-kW operation



Residual dose is almost proportional to the beam power.


- No beam loss specific to 1-MW operation was observed.

# Continuous operation with 1MW (RCS)




## Comparison of residual dose at 1-MW and 600-kW operation

### Beam current at 1 MW



✓ No significant loss

After 1 MW, 40 hr trial for MLF (27th Jun. 2020), Measurement after 5 hours from beam stop 600 kW user operation (24th Jun. 2020) , Measurement after 4 hours from beam stop



- Residual dose is almost proportional to the beam power.
  - No beam loss specific to 1-MW operation was observed as well as linac.

# Summary




- Beam commissioning of the J-PARC accelerator started in 2006 (linac).
- In JFY2021, the accelerator provided beams of up to **740 kW to MLF**, **510 kW to Nu**, and **64 kW to HD**, respectively.
- In JFY2021, the availability of the accelerator achieved **96% for MLF** and **93% for NU and HD**.
- In JFY2022, the MLF beam power is increased to **800 kW** for user operation.
- Continuous operation with a beam power equivalent to **1 MW** was conducted, and it was confirmed that there were **no critical issues** in both linac and RCS, such as a significant increase in beam loss or an increase in the trip rate of the accelerator components.

**Thank you for your attention !**

**Buck up slide**

# Layout of linac components

- The J-PARC linac consists of an **ion source** and four types of accelerating cavities (**RFQ**, **DTL**, **SDTL** and **ACS**), and is installed in an accelerator tunnel approximately 13 meters underground.
- The RFQ, DTL and SDTL are driven by **324-MHz klystrons**, and the ACS is driven by **972-MHz klystrons**. These klystrons are installed in a 330-m-long room called the klystron gallery at ground level.




# Layout of RCS components

- We have chosen the lattice with **three-folding symmetry** in order to keep three long straight sections (**injection section, RF acceleration section and extraction section**).

The stripping foil in the injection section is used to convert  $H^-$  beam from the linac into protons.




The H0 dump is used to dump un-stripped beams at the stripping foil. The capacity is 4kW.




The beams are extracted by kicker magnets and DC septum magnets at the extraction section, and then transported either to MLF or to MR with a pulsed bending magnet placed in the 3NBT line.

Twelve RF cavities in total are installed in the tunnel, whereas an accelerating electric field is excited by applying an RF power fed using the tetrode.

# Time structure of accelerator operation



RCS operation cycle



MR operation cycle