


# **J-PARC Neutron-Muon facility construction, commissioning and operation of Target, Moderator and Instruments**

**October 10, 2022**

**Hiroshi Takada, Kazuya Aizawa, Toshiya Otomo  
Materials and Life Science Division  
J-PARC Center**



# Operations of MLF in J-PARC

- Operations and control of accelerators are conducted at central control building.
- Operations and control of Neutron Source, Muon target and beamlines are conducted at MLF.
- Interlock signals (PPS, MPS, etc.) of MLF are transferred to accelerator control system to stop beam .



# Outline of Materials and Life Science Experimental Facility MLF


|                            |                             |
|----------------------------|-----------------------------|
| Neutron production target  | Hg                          |
| Moderator                  | LH <sub>2</sub> (para 100%) |
| Reflector                  | Be/Fe                       |
| Number of neutron beamline | 23                          |
| Number of neutron shutter  | 23                          |



## Radiation shielding design criteria

- Dose rate at boundary of radiation controlled area: < 12.5  $\mu\text{Sv/h}$
- Dose rate at boundary of non-radiation controlled area: < 0.25  $\mu\text{Sv/h}$
- Dose under operating period 25  $\mu\text{Sv/h}$

# Pulsed spallation neutron source of MLF



Proton beam window

Proton beam  
3 GeV, 1MW, 25 Hz

Moderators

Shielding

Shielding

Neutron shutter


neutron

Outer liner

Cryogenic hydrogen system




Mercury target system

5m





# Pulsed spallation neutron source facility


- Clear separation of the user area from the source components operation/ maintenance area
- Appropriate and effective facility layout considering components maintenance;
  - Hot-cell for handling highly irradiated components
  - High bay structure




# Remote handling devices in hot cell




# Construction Schedule of MLF -- Neutron and Muon Sources --



# Example of beamline shielding design




Plane section of calculation model for BL10



- 3-D Monte Carlo calculation with PHITS code
- Neutrons generated at moderator surface with directional cosine viewing inside beam duct are considered as source spectra.
- Design target is less than  $12.5 \mu\text{Sv/h}$ .
- Safety margin of factor 2 is considered in PHITS calculation.
- When a neutron beamline is increased, shielding calculation is carried out with modelling all beamline and source spectra.

Calculated dose rate in case of using steel sample





# View of outside of neutron source station

Pre-shield installation along each beam lines in 2007

Outer face of the station




Neutron beam collimator shield installation




Shield plug for unused beamline



# MLF experimental Hall #1 in 2007




# MLF experimental Hall #2 in 2007



# Neutron beam line construction in FY2007


## Experimental Hall #1



## Experimental Hall #2



# Status of neutron instruments in 2008 - 1<sup>st</sup> year of operation



- 7 Instruments are open for user program.
- 4 Instruments have been working from Dec. '08.
- 1 Instrument is under construction.
- 3 Instrument are newly funded (two for JAEA and 1 for U. Tokyo & JAEA).

# Flow of neutron source component construction

## Example: Mercury target system

Design of neutron source system by MLF construction team with Building construction department of JAEA



Design and fabrication of each component by procurement



Subsystem and integrated tests of a component by a vendor



On-site integration tests and commissioning by MLF construction team

### Procurement items


- ✓ Target vessel
- ✓ Hg circulation system with target trolley

### Subsystem and integrated test of component:

- ✓ Remote handling test using crane,
- ✓ Seal performance test, etc.

### On-site integration tests and commissioning:


- ✓ Remote handling test with manipulators,
- ✓ Seal performance test,
- ✓ Water loop test, Hg loop test, etc.



# Integration tests and commissioning

- Integration tests from April 2007 to March 2008
  - Target installation and Hg circulation
  - Moderator installation and Liq. H<sub>2</sub> circulation
  - Water cool, gas insulation, ventilation, etc.
  - BT commissioning (Dump mode Sept. 2007)
  - Remote handling and control system validation
- On beam commissioning; May 2008
- 20 kW beam operation; Oct. 2008
  - With seven Day-one instruments

Remote handling tests :2007.03 -



# Control system validation for neutron shutter and beamline





Procedure to access to sample room of neutron instrument

**Shutter CLOSE** ⇒ Pull off **two safety keys** from key panel and insert one of keys into Door Controller  
⇒ Unlock the door and enter to sample room

Procedure to use neutron beam

Sweep all users out of sample room ⇒ **Lock the door**  
⇒ Release the key from Door controller  
⇒ **Return it to key panel**  
⇒ **Shutter open permission**

It is designed that shutter is never opened unless all keys are returned to the key panel





# Readiness checklist

---

- Objectives to check readiness
  - to list all necessary conditions which are needed to be completed before the beam acceptance, and
  - to share the checklists among those who are in charge of neutron source construction and operation for mutual confirmation.
- This procedure is effective
  - to avoid forgetting to do something important before the beam acceptance, and
  - to make acceptance criteria clear.

*Total 700 items are included in readiness checklist for all MLF components.*

# Example of readiness sheet

Component: Moderator

Last modified: Jan. 04, 2008

| General item  | Detailed item  | Acceptance Criteria  | Confirmation methods<br>(Name of document)      | Necessity<br>A: Indispensable<br>by Day-1<br>B: Preferable by<br>Day-1 | Status<br>A: Completed<br>B: Conditionally<br>Completed<br>C: Not yet<br>Completed |
|---------------|--|--|---|--|--|
| 1.1 Functions | Moderators have been installed at the right positions. Pressure proof and leak tests have been passed after connecting to the hydrogen circulation system. | Hydrogen region<br>Pressure proof test: 1.5 MPa<br>Leak rate: not detectable by He-leak test<br>Vacuum region<br>Leak rate: not detectable by He-leak test<br>He-blanket region<br>Leak rate: not detectable by He-leak test<br>Cooling water region | Off-beam commissioning report                   | A  | C  |
|               | Stable operations of hydrogen, vacuum, He-blanket and cooling water systems at the nominal conditions have been confirmed.                                 | Hydrogen system: OK<br>Vacuum system: OK<br>He-blanket system: OK<br>Cooling water system: OK  | Off-beam commissioning report                   | A  | C  |
|               | Integrity of cryogenic temperature region has been confirmed.  | Unexpected contact between cold and room temperature regions: No   | Off-beam commissioning report                   | A  | C  |
|               | Arrangement with the process control system has been completed.  | NA   | NETH transmission list<br>Console display pages | A  | C  |

# Format of Readiness

---

**1st column:** General items

functions, process operation, maintainability, measures for off-normal events, *etc.*

**2nd column:** Detailed items

**3rd column:** Acceptance criteria for each detailed item.

- Only major acceptance criteria are described in this checklist while detailed and many other acceptance criteria are dropped for simplification.
- Other documents such as documents prepared by manufacturer and technical reports can be referred in the checklist if needed.

**4th column:** Confirmation method to satisfy the acceptance criteria


- The confirmation should rely on **documents** as much as possible that are accessible by any interested persons of JSNS in order to be checked by third persons from an objective point of view.

Examples of the documents:

documents prepared by manufacturer, technical reports, papers, etc.

# The first neutron production at JSNS


May 30, 2008, 14:25 at BL10 (NOBORU) the first neutron beam was observed. Right after on May 30 and May 31, BL3, BL4, BL8, BL20 were tested with 0.4 Tp/shot. (single shot mode) in total 2,500 shots.



# Example of on-beam commissioning results


Resolution and intensity at neutron instruments were measured, resulting that source performance was confirmed as what is expected.

SuperHRPD(BL08) :  $\Delta d/d = 0.035\%$



Neutron pulse shape measured at sample position of Super High Resolution Powder Diffractometer (BL08) which is provided by poisoned moderator with a Cd plate

Intensity at BL01 (Dec. 25, 2008)





Neutron intensity at sample position of BL01 which is provided by coupled moderator

# Validation of neutronic performance of beamline

Once a beamline is completed and/or realigned, neutron flux and intensity are measured with PSD and foil activation for validation.

## Experience at BL19 having curved guides



- Measured neutron flux was lower than the estimated one by about 50-60%, indicating that beamline was mis-aligned.
- As a matter of fact, the vacuum jackets had been aligned to opposite direction.



# Example of on-beam commissioning results

## Target design confirmation at 120 kW


- Temperature rising at mercury vessel by 120 kW beam power agreed with the design estimation.
- As results, it was confirmed that the mercury circulation system; EM pump, heat exchanger, etc., were operated sufficiently as expected in the design.



# Validation of Neutron Beamline Shield

- In 2014, dose rates outside shields at neutron source, muon source, and all beam lines were measured at a beam power of 300-kW.
- Some weak points were found by this measurement, and repaired.

Example: BL14 case





# Summary

---

- Pulsed neutron source components of MLF was designed and fabricated to receive 1-MW proton beam.
- On-site integration tests and commissioning were carried out from 2007 to May 2008 during which items to be completed up to Day-1 were specified using readiness checklist.
- Intensity and pulse shape of neutron beam provided by the neutron source was validated at each neutron beam line during on-beam commissioning, resulting that neutron performance was what as it expected.
- On-beam test was useful to find misalignment of a neutron beam component and confirm shield performance around sample room of a neutron instrument.