

# Cold tests of bulk Nb cavities at CERN

**Katarzyna Turaj**

on behalf of


**S. Barriere, A. Castilla, B. Frere-Bouniol, P. Fernandez Lopez,  
K. Hernandez Chahin, A. Macpherson, K. M. Schirm,  
N. Shipman, N. Stapley, A. Zwozniak, M. Wartak**

# Bulk Nb Cavity Testing at CERN

- RF cavity testing at CERN's SM18 Facility:
  - 400 MHz Crab Cavities (Bare & Dressed) & Cavity Tuners
  - 704 MHz High Gradient Program,
  - 1.3 GHz cavity R&D



**1980**



**2017**

# CERN's Bulk Niobium Program: Overview

---

## • HL-LHC Crab Cavity

- RF validation of bare and dressed 400MHz cavities for SPS
- Cryomodule assembly and validation
- Installation into CERN SPS for validation with proton beams (2018)

## • High Gradient Cavity Program

- Prepare and validate 5-cell  $\beta=1$  704 MHz cavities
- Bring 4 cavities to specification for assembly
- Assembly into a cryomodule for RF validation in CERN's SM18 facility

## • Process and Diagnostics development

- Cleanroom techniques and cavity assembly procedures
- RF surface preparation improvement
- Diagnostics for Quench localization,
- Bulk and surface RRR measurements
- Cooldown techniques, control of flux trapping


# Recent Activities: Key Points

---

- **Over the last 12 months**
  - Upgrade of infrastructure interleaved with cavity testing
  - Ongoing upgrade of our 4m & 2m cryostats
  - ~ 9 months for RF Testing
    - Dominated by RF tests on Crab Cavities
- **HG Cavity Performance: Specification achieved**
  - Validated upgraded electro-polishing cathode design
    - Chemistry now proceeding on remaining cavities
- **Cleanroom assembly process**
  - Process and infrastructure reviewed for Crab project
    - Cavity handling and assembly more controlled & cleaner

# Schedule from first half of 2017

- Last 12 months dominated by HL-LHC Crab activity
  - High Gradient RF tests “squeezed in”




# 2016 Results: High Gradient

## SLHiPP-6

- Improvements from cavity preparation significantly reduced field emission resulting in improved RF cavity performance

March 2016


September 2014



# 2017 Results: High Gradient

- Continued improvement in preparation & test procedure  
=> reduced field emission & reach specification



$Q_0 > 10^{10}$  at  $E_{acc} = 25$  MV/m





# Performance Measurements

- All scans performed in CW operation @ 2K
  - Scan increments in watts => detailed scan at high power
- Field emission above 20MV/m
  - => Cavity assembly still to be improved
- Moving to Self Excited Loop system
  - Improvement of measurement uncertainties







# Quench studies







- **32 sensor array of OSTs**
  - Readout based on CEA-Saclay design
  - Resolved issues with signal loss
    - Signal lines in cryostat replaced (coax→ twisted pair)
  - Cleaned up signal to noise ratio by isolating OSTs from cavity and cryostat infrastructure
- **Test new Transition Edge Sensors for quenches**
  - Offers improved positioning resolution

*Hernán Furci's talk*




# Quenches - 3 Varieties Observed

- **Local Quench**
  - Slow quench
    - Cell 1 equator
  - 2<sup>nd</sup> sound velocity
    - $V = 12.4$  m/s
- **Global Quench**
  - Fast quench
    - cell 3 equator
  - No localisation
  - 2<sup>nd</sup> sound velocity
    - $V = 18$  m/s
- **Double quench**
  - Small quench without cavity trip





# In-situ bulk RRR measurement

- **Standard 4-wire resistance measurement**
  - Measurement at 300K and at 10K
  - Resistance at 10 K:  $R \sim 0.2 \mu\Omega$
  - **Fixation of wires to cavity is critical**
- **Procedure validated on Crab Cavities**



Cavity	Resistance at 300K $\mu\Omega$	Resistance @ 10K $\mu\Omega$	RRR
DQW SPS 1	64.247 +- 0.282	0.189 +- 0.025	340 $\pm$ 45
DQW SPS 2	49.022 $\pm$ 0.112	0.130 $\pm$ 0.005	377 $\pm$ 15

RRR on treated Nb samples = 290  $\pm$  30





# Upgraded Cryo Insert - Validated in 2016

- Improved insulation & cryostat now leak free
  - Influx heat flow reduced & electrical grounding scheme
- Cavity positioned lower in cryostat
  - Larger head of liquid Helium above cavity



**OLD INSERT**




**NEW INSERT**




# Infrastructure: Cryostat insert upgrade

- **New 'top' of vertical cryostat commissioned**
  - Insert assembly, installation & load balancing
- **Vacuum pumping system replaced**
  - Increased diagnostics (including RGAs added)
  - Pneumatic valves on pumping line:
    - Avoids ambient B-field issues when opening shielding




# Improvements - Mobile Coupler

- **Switch to mobile coupler in Q3 2017**
  - Test power antenna re-designed for beam port
  - Coupler designed to work in 2K liquid helium
  - 50 mm range of movement
    - => can have critical coupling from 10K to 1.8K**
  - Will allow improved conditioning and cavity processing




Mass 7 Kg



Courtesy of E. Montesinos and team

# Cleanroom Practices


- **Post 2016 HL-LHC Crab Cavity cleanroom tooling review**
  - Re-tooling and improvement of ISO4 cleanroom infrastructure and practices
  - Reinforcement of cleanroom floor and purchase of cleanroom lifter matched to project needs
  - Removal of silver coated nuts/bolts from cavity assembly
    - Using silicon bronze nuts for flange assembly
  - Improved pre-assembly cleaning of pieces





# Other Improvements

- **Cleaner connection of cavity to insert pumping line**
- **Reduction of contamination during 650°C vacuum bake**
  - Use niobium caps on all ports during bakeout
- **Improved prep of cavity immediately prior to HPR**
  - Ultrasonic bath after final chemistry essential



# Outlook

---

- **HL-LHC Crab Cavity Program**
  - Vertical Cryostat RF tests continue through 2017
- **High Gradient Program: 4 Cavities**
  - HG1: Chemistry re done → Preparing for RF Test
  - HG2: Achieved Specification: Now our reference cavity
  - HG3: Bulk EP done. Sent to vacuum oven for 650°C bake
  - HG4: Waiting for EP
- **High Gradient Program: Cavity Testing**
  - RF tests to be interleaved with Crab program in 2017
  - Combine with commissioning of mobile coupler
- **Bulk Niobium program**
  - Target: 1 RF cold test per month per cryostat
  - 2nd cryostat coming on line in Q3 2017

# Summary

---

- **CERN's Bulk Niobium program**
  - dominated by Crab cavity activities at present
  - ... but still progressing with the High Gradient Program
  - Soon to have 2 vertical cryostats dedicated to RF testing of bulk Niobium cavities
- **High Gradient: One cavity has reached specification**
  - Other three cavities to under go same treatment/testing
  - Expect to finish initial test on all 4 cavities by Q1 of 2018
- **Ongoing developments**
  - Cataloging of quench behaviors and quench spot localisations prior to optical inspection
  - Validated deployment of Self Excited Loop LLRF system and semi automation of test procedures
  - Integration of mobile coupler into conditioning process

# Thank you

