Freia Product Breakdown Structure

Version 6.4 07/12/17
Author: Jim Nightingale

- 13.6.11 FREIA
  - 13.6.11.1 Beam Transport and Conditioning System
    - 13.6.11.1.1 Beam Extraction System
      - 13.6.11.1.1.1 Monolith Insert
      - 13.6.11.1.1.2 Monolith Insert Alignment Mechanism
      - 13.6.11.1.1.3 Insert Vacuum Windows
    - 13.6.11.1.2 Beam Delivery System
      - 13.6.11.1.2.1 Neutron Supermirror Guide
        - 13.6.11.1.2.1.1 Guide Bender (NBOA monolith insert)
        - 13.6.11.1.2.1.2 Guide Section (Light Shutter)
        - 13.6.11.1.2.1.3 Guide Sections (In bunker)
        - 13.6.11.1.2.1.4 Guide Section (Heavy shutter)
        - 13.6.11.1.2.1.5 Guide Sections (Bunker Wall)
        - 13.6.11.1.2.1.6 Guide sections (out of Bunker)
        - 13.6.11.1.2.1.7 Collimation Guide #1
        - 13.6.11.1.2.1.8 Collimation Guide #2
        - 13.6.11.1.2.1.9 Collimation Guide #3
      - 13.6.11.1.2.2 Neutron Guide vacuum housing, support & alignment
      - 13.6.11.1.2.3 Neutron Guide Streaming Shielding
    - 13.6.11.1.3 Chopper System
      - 13.6.11.1.3.1 Wavelength Band Definition Chopper System WBC1
      - 13.6.11.1.3.2 Wavelength Band Definition Chopper System WBC2
      - 13.6.11.1.3.3 Wavelength Band Definition Chopper System WBC3
      - 13.6.11.1.3.4 Wavelength Frame multiplication chopper system WFM1
      - 13.6.11.1.3.5 Wavelength Frame multiplication chopper system WFM2
      - 13.6.11.1.3.6 Frame overlap Chopper FOC1
      - 13.6.11.1.3.7 Frame overlap Chopper FOC2
      - 13.6.11.1.3.8 Frame overlap Chopper FOC3
      - 13.6.11.1.3.9 Chopper Housings (CHIM)
      - 13.6.11.1.3.10 Control Systems
      - 13.6.11.1.3.11 Systems Support
        - 13.6.11.1.3.11.1 EPICS IOC
      - 13.6.11.1.3.12 Service package
    - 13.6.11.1.4 Beam Geometry Conditioning
      - 13.6.11.1.4.1 Guide Collimation system
        - 13.6.11.1.4.1.1 Guide Changer Vacuum housing
        - 13.6.11.1.4.1.2 Guide changer Translation and Guide Mounting
      - 13.6.11.1.4.2 Slit Collimation systems
        - 13.6.11.1.4.2.1 XY Slits #1 Reflectometry
        - 13.6.11.1.4.2.2 XY Slits #2 Reflectometry
        - 13.6.11.1.4.2.3 Sample Attenuator
        - 13.6.11.1.4.2.4 XY Slits Sample
        - 13.6.11.1.4.2.5 XY Slits Beamstop
        - 13.6.11.1.4.2.6 GiSANS Slits #1 - NOT IN SCOPE
        - 13.6.11.1.4.2.7 GiSANS Slits #2 - NOT IN SCOPE
        - 13.6.11.1.4.2.8 GiSANS Slits #3 - NOT IN SCOPE
        - 13.6.11.1.4.9 Time-Resolved Slit System
          - 13.6.11.1.4.9.1 3 slit system #1
          - 13.6.11.1.4.9.2 3 slit system #2
          - 13.6.11.1.4.9.3 Fast Time-resolved system- NOT IN SCOPE
    - 13.6.11.1.5 Beam Filtering System - NOT IN SCOPE
      - 13.6.11.1.5.3 Neutron Polarisation System - NOT IN SCOPE
      - 13.6.11.1.5.4 Neutron Spin Flipper - NOT IN SCOPE
    - 13.6.11.1.6 Beam Validation
      - 13.6.11.1.6.1 Beam monitors
        - 13.6.11.1.6.1.1 Diagnostic Monitors (chopper)
        - 13.6.11.1.6.1.2 Normalisation Monitors
        - 13.6.11.1.6.1.3 Beam Monitor Electronics
        - 13.6.11.1.6.1.4 EPICS IOC
    - 13.6.11.1.8 Beam Cut Off
      - 13.6.11.1.8.2 Heavy shutter
        - 13.6.11.1.8.2.1 Shutter Housing
        - 13.6.11.1.8.2.2 Motion Mechanics
      - 13.6.11.1.8.7 Light shutter Components
        - 13.6.11.1.8.7.1 Light shutter guide housing
    - 13.6.11.1.9 Vacuum System
      - 13.6.11.1.9.5 In-bunker vacuum system
      - 13.6.11.1.9.6 Out-of-bunker vacuum system
    - 13.6.11.1.10 Shielding
      - 13.6.11.1.10.1 Bunker components shielding
      - 13.6.11.1.10.2 Beamline Shielding (bunker to cave)
      - 13.6.11.1.10.4 Bunker wall insert
  - 13.6.11.2 Sample Exposure System
    - 13.6.11.2.1 Sample Positioning (sample stack)
    - 13.6.11.2.3 Sample Environment - NOT IN SCOPE
    - 13.6.11.2.4 Non-sample Environment
      - 13.6.11.2.4.1 Sample Alignment Components
      - 13.6.11.2.4.2 Sample area web cams
      - 13.6.11.2.4.5 Sample Access Structures & Components
  - 13.6.11.3 Sample Scattering characterisation system
    - 13.6.11.3.2 Neutron Detector System
      - 13.6.11.3.2.1 Neutron Detector
        - 13.6.11.3.2.1.1 300x300mm Boron Blade Detector
        - 13.6.11.3.2.1.2 Detector Electronics (reduced area)
        - 13.6.11.3.2.1.3 Detector DAQ
        - 13.6.11.3.2.1.4 Detector Readout (DMSC)
        - 13.6.11.1.3.1.5 Epics IOC
      - 13.6.11.3.2.2 Neutron Detector positioning system (bench, alignment and mounting)
      - 13.6.11.3.2.3 Detector vessel for gas system / vacuum system
    - 13.6.11.1.3.3 Vacuum System
      - 13.6.11.1.3.3.2 Detector Vacuum System
      - 13.6.11.1.3.3.3 Detector Gas systems (if needed)
  - 13.6.11.5 Experimental Cave
    - 13.6.11.5.2 Utilities Distribution (see Breakout
    - 13.6.11.5.3 Support Infrastructure (See Breakout)
    - 13.6.11.5.4 Shielding
    - 13.6.11.5.5 Cave Structure
      - 13.6.11.5.5.1 Cave walls and roof
      - 13.6.11.5.5.2 Beamstop
      - 13.6.11.5.5.3 Door
      - 13.6.11.5.5.4 Raised Floor
      - 13.6.11.5.5.5 Equipment Lift
      - 13.6.11.5.5.6 Internal Crane
    - 13.6.11.5.6 Sample Environment Utilities supply
    - 13.6.11.5.7 Sample environment control box
  - 13.6.11.6 Control Hutch
    - 13.6.11.6.1 Support Infrastructure (See Breakout)
    - 13.6.11.6.2 Hutch construction
      - 13.6.11.6.2.1 Hutch Structure
      - 13.6.11.6.2.2 Hutch Furniture
    - 13.6.11.6.3 Control terminal
  - 13.6.11.7 Sample Preparation Area
    - 13.6.11.7.1 Utilities Distribution (see Breakout)
    - 13.6.11.7.2 Support Infrastructure (See Breakout)
    - 13.6.11.7.3 Sample Preparation Area construction - NOT IN SCOPE
    - 13.6.11.7.4 Laboratory equipment and sample storage - NOT IN SCOPE
    - 13.6.11.7.5 Furniture - NOT IN SCOPE
  - 13.6.11.8 Utilities Distribution (see Breakout)
    - X Utilities Distribution
      - X.1 Power distribution
      - X.2 Chilled Water Distribution
      - X.3 Compressed Air Distribution
      - X.4 Gas Distribution
      - X.5 EPICS IOC
  - 13.6.11.9 Support Infrastructure (See Breakout)
    - X Support Infrastructure
      - X.1 Power
      - X.2 Network
      - X.3 Lighting
      - X.4 Ventilation (HVAC)
      - X.5 Fire protection
      - X.6 Local Crane Services
      - X.7 Public Address System
      - X.8 Cable Trays
      - X.9 EPICS IOC
  - 13.6.11.10 Control Racks
    - 13.6.11.10.1 DAQ Racks
    - 13.6.11.10.2 DMSC Racks
    - 13.6.11.10.3 Motion Control Racks
    - 13.6.11.10.4 Chopper CHIC Racks
    - 13.6.11.10.5 Vacuum Control Racks
    - 13.6.11.10.6 Personal Safety System Racks
  - 13.6.11.11 Integrated control and monitoring
    - 13.6.11.11.1 Instrument control integration
      - 13.6.11.11.1.1 Generic Motion Control Integration
      - 13.6.11.11.1.2 Special Purpose Motion Control Integration
      - 13.6.11.11.1.4 Control Racks and electronics (MCA Integration)
      - 13.6.11.11.1.6 EPICS Integration
    - 13.6.11.11.2 PSS (See Breakout)
      - X Personal Safety System (PSS)
        - X.1 Interlock System
        - X.2 Radiation Detection
        - X.3 Shutter Interface
        - X.4 H2O Detection System
        - X.5 O2 Monitoring
        - X.6 H2 Detection System
    - 13.6.11.11.3 Data Management and Sofware Centre DMSC
      - 13.6.11.11.3.1 Data System and Technology
      - 13.6.11.11.3.2 Data Management
      - 13.6.11.11.3.3 Instrument Data
      - 13.6.11.11.3.4 Data Analysis and Modelling
    - 13.6.11.11.4 Vacuum Control Integration VCI
      - 13.6.11.11.4.1 VCI Components
      - 13.6.11.11.4.2 VCI Sequency
      - 13.6.11.11.4.3 Epics IOC
      - 13.6.11.11.4.4 Vacuum control Racks and electronics